

May 2023

Stack Storage - 2118 Hanover Avenue Anticipated Sewage Flow Calculations

| | |
|-------------------------------|--------------|
| Employees | 2 * |
| Water Use Per Employee | 35 (gal/day) |
| Total Water Use | 70 (gal/day) |

Source: PA Code Chapter 73.17

***Maximum number of employees anticipated per day**